SPECIFICATION SUBMITTAL SHEET



Schedule 40 Waste & Overflow - Classic High-flow Half Kit w/Test Kit

| Job Name: | _ Contractor: |
|---------------|-------------------|
| Job Location: | Approval: |
| Engineer: | Contractor's PO#: |
| Approval: | _ Representative: |

Specification:

Series 2217

"Classic" High-flow Bath Waste & Overflow Half Kit (Less Pipe and Tee) with Test Kit Test kit rated up to 4 stories
Brass Strainer 1-1/2 x 11-1/2" Pipe Size and Push eN Lift Closure

UPC Listed
Manufactured to ASME Standard
ASME A 112.18.2-2005 / CSA B 125.2-05



1-3/16"

| Qty | AB&A Part# | Item # | Material | Finish | Notes |
|-----|------------|--------|----------|-------------------|------------------------------------|
| | 2217HF | 62001 | ABS | Chrome | |
| | 2217ZHF | 62003 | ABS | Chrome | With Zinc Strainer |
| | 2217PZHF | 62002 | ABS | Chrome | With Zinc Strainer and ABS Stopper |
| | 2217MHF | 62486 | ABS | Chrome | With Metal Test Kit (not pictured) |
| | 2221SNHF | 62005 | ABS | Satin Nickel | |
| | 2221VBHF | 62006 | ABS | Venetian Bronze | |
| | 2221ORBHF | 62004 | ABS | Oil Rubbed Bronze | |
| | 2218HF | 62007 | PVC | Chrome | |
| | 2218ZHF | 62038 | PVC | Chrome | With Zinc Strainer |
| | 2218PZHF | 62037 | PVC | Chrome | With Zinc Strainer and ABS Stopper |
| | 2218MHF | 62487 | PVC | Chrome | With Metal Test Kit (not pictured) |
| | 2222SNHF | 62009 | PVC | Satin Nickel | |
| | 2222VBHF | 62092 | PVC | Venetian Bronze | |
| | 2222ORBHF | 62008 | PVC | Oil Rubbed Bronze | |

