Tranquility® 30 (TT) Series Rev.: October 7, 2016

Preventive Maintenance

Water Coil Maintenance - (Direct ground water applications only) If the system is installed in an area with a known high mineral content (125 P.P.M. or greater) in the water, it is best to establish a periodic maintenance schedule with the owner so the coil can be checked regularly. Consult the well water applications section of this manual for a more detailed water coil material selection. Should periodic coil cleaning be necessary, use standard coil cleaning procedures, which are compatible with the heat exchanger material and copper water lines. Generally, the more water flowing through the unit, the less chance for scaling. Therefore, 1.5 gpm per ton [1.6 I/m per kW] is recommended as a minimum flow. Minimum flow rate for entering water temperatures below 50°F [10°C] is 2.0 gpm per ton [2.2 I/m per kW].

Water Coil Maintenance - (All other water loop applications) Generally water coil maintenance is not needed for closed loop systems. However, if the piping is known to have high dirt or debris content, it is best to establish a periodic maintenance schedule with the owner so the water coil can be checked regularly. Dirty installations are typically the result of deterioration of iron or galvanized piping or components in the system. Open cooling towers requiring heavy chemical treatment and mineral buildup through water use can also contribute to higher maintenance. Should periodic coil cleaning be necessary, use standard coil cleaning procedures, which are compatible with both the heat exchanger material and copper water lines. Generally, the more water flowing through the unit, the less chance for scaling. However, flow rates over 3 gpm per ton (3.9 l/m per kW) can produce water (or debris) velocities that can erode the heat exchanger wall and ultimately produce leaks.

Hot Water Generator Coils - See water coil maintenance for ground water units. If the potable water is hard or not chemically softened, the high temperatures of the desuperheater will tend to scale even quicker than the water coil and may need more frequent inspections. In areas with extremely hard water, a HWG is not recommended.

Filters - Filters must be clean to obtain maximum performance. Filters should be inspected every month under normal operating conditions and be replaced when necessary. Units should never be operated without a filter.

Washable, high efficiency, electrostatic filters, when dirty, can exhibit a very high pressure drop for the fan motor and reduce air flow, resulting in poor performance. It is especially important to provide consistent washing of these filters (in the opposite direction of the normal air flow) once per month using a high pressure wash similar to those found at self-serve car washes.

Condensate Drain - In areas where airborne bacteria may produce a "slimy" substance in the drain pan, it may be necessary to treat the drain pan chemically with an algaecide approximately every three months to minimize the problem. The condensate pan may also need to be cleaned periodically to ensure indoor air quality. The condensate drain can pick up lint and dirt, especially with dirty filters. Inspect the drain twice a year to avoid the possibility of plugging and eventual overflow.

Compressor - Conduct annual amperage checks to ensure that amp draw is no more than 10% greater than indicated on the serial plate data.

Fan Motors - All units have lubricated fan motors. Fan motors should never be lubricated unless obvious, dry operation is suspected. Periodic maintenance oiling is not recommended, as it will result in dirt accumulating in the excess oil and cause eventual motor failure. Conduct annual dry operation check and amperage check to ensure amp draw is no more than 10% greater than indicated on serial plate data.

Air Coil - The air coil must be clean to obtain maximum performance. Check once a year under normal operating conditions and, if dirty, brush or vacuum clean. Care must be taken not to damage the aluminum fins while cleaning. When the heat pump has experienced less than 100 operational hours and the coil has not had sufficient time to be "seasoned", it is necessary to clean the coil with a mild surfactant such as Calgon to remove the oils left by manufacturing processes and enable the condensate to properly "sheet" off of the coil. CAUTION: Fin edges are sharp.

Cabinet - Do not allow water to stay in contact with the cabinet for long periods of time to prevent corrosion of the cabinet sheet metal. Generally, vertical cabinets are set up from the floor a few inches [7 - 8 cm] to prevent water from entering the cabinet. The cabinet can be cleaned using a mild detergent.

Refrigerant System - To maintain sealed circuit integrity, do not install service gauges unless unit operation appears abnormal. Reference the operating charts for pressures and temperatures. Verify that air and water flow rates are at proper levels before servicing the refrigerant circuit.

CLIMATEMASTER WATER-SOURCE HEAT PUMPS

Tranquility® 30 (TT) Series Rev.: October 7, 2016

Functional Troubleshooting

Fault	Htg	Clg	Possible Cause	Solution		
				Check line voltage circuit breaker and disconnect.		
Main newer nuchlama			Create Otation LED Off	Check for line voltage between L1 and L2 on the contactor.		
Main power problems	^	^	Green Status LED Off	Check for 24VAC between R and C on CXM/DXM'		
				Check primary/secondary voltage on transformer.		
		v		Check pump operation or valve operation/setting.		
		X	Reduced or no water flow in cooling	Check water flow adjust to proper flow rate.		
		Х	Water Temperature out of range in cooling	Bring water temp within design parameters.		
HP Fault			· · · · · · · · · · · · · · · · · · ·	Check for dirty air filter and clean or replace.		
Code 2				Check fan motor operation and airflow restrictions.		
	^		Reduced of no air flow in heating	Dirty Air Coil- construction dust etc.		
High Pressure				Too high of external static. Check static vs blower table.		
	Х		Air temperature out of range in heating	Bring return air temp within design parameters.		
	Х	Х	Overcharged with refrigerant	Check superheat/subcooling vs typical operating condition table.		
	Х	Х	Bad HP Switch	Check switch continuity and operation. Replace.		
LP/LOC Fault	Х	Х	Insufficient charge	Check for refrigerant leaks		
Code 3						
	X		Compressor pump down at start-up	Check charge and start-up water flow.		
Low Pressure / Loss of Charge						
				Check pump operation or water valve operation/setting.		
LT1 Fault	X		Reduced or no water flow in heating	Plugged strainer or filter. Clean or replace		
Code A				Check water flow adjust to proper flow rate.		
0000 4	X		Inadequate antifreeze level	Check antifreeze density with hydrometer.		
Water coil low	x		Improper temperature limit setting (30°F vs	Clip JW3 jumper for antifreeze (10°F [-12°C]) use.		
temperature limit			10°F [-1°C vs -2°C])			
	X		Water Temperature out of range	Bring water temp within design parameters.		
	X	X	Bad thermistor	Check temp and impedance correlation per chart		
				Check for dirty air filter and clean or replace.		
LT2 Fault		X	Reduced or no air flow in cooling	Check fan motor operation and airflow restrictions.		
Code 5				Too high of external static. Check static vs blower table.		
		Х	Air Temperature out of range	Too much cold vent air? Bring entering air temp within design parameters.		
Air coil low		x	Improper temperature limit setting (30°F vs	Normal airside applications will require 30°F [-1°C] only.		
temperature limit		~	10°F [-1°C vs -12°C])			
	X	X	Bad thermistor	Check temp and impedance correlation per chart.		
	X	X	Blocked drain	Check for blockage and clean drain.		
	×	X	Improper trap	Check trap dimensions and location ahead of vent.		
				Check for piping slope away from unit.		
Condensate Fault		X	Poor drainage	Check slope of unit toward outlet.		
Code 6				Poor venting. Check vent location.		
		X	Moisture on sensor	Check for moisture shorting to air coil.		
	×	×	Plugged air filter	Replace all mitter.		
	X		Restricted Return Air Flow	Find and eliminate restriction. Increase return duct and/or gnile size.		
		x	Under Voltage	Check power supply and 24VAC voltage before and during operation.		
Over/Under	x			Check power supply wire size.		
Voltage Code 7				Check compressor starting. Need hard start kit?		
				Check 24VAC and unit transformer tap for correct power supply voltage.		
(Auto resetting)	X	х	Over Voltage	Check power supply voltage and 24VAC before and during operation.		
	v		Heating mode LT2> 125°E [52°C]	Check for poor air flow or oversborged unit		
Unit Performance Sentinel	^		Capling Mode LT2>T25 F [52 C]			
Code 8		Х	40°F [4°C])	Check for poor water flow, or air flow.		
Swapped Thermistor	X	х	LT1 and LT2 swapped	Reverse position of thermistors		
Code 9						
	X	Х	No compressor operation	See "Only Fan Operates".		
No Fault Code Shown	X	Х	Compressor overload	Check and replace if necessary.		
	X	Х	Control board	Reset power and check operation.		
	X	X	Dirty air filter	Check and clean air filter.		
Unit Short Cycles	X	X	Unit in "test mode"	Reset power or wait 20 minutes for auto exit.		
	X	X	Unit selection	Unit may be oversized for space. Check sizing for actual load of space.		
	X	X	Compressor overload	Check and replace if necessary		
	X	Х	Thermostat position	Ensure thermostat set for heating or cooling operation.		
	X	Х	Unit locked out	Check for lockout codes. Reset power.		
Only Fan Runs	X	X	Compressor Overload	Check compressor overload. Replace if necessary.		
	x	x	Thermostat wiring	Check thermostat wiring at heat pump. Jumper Y and R for compressor operation		
			Ű	In test mode.		
	X	х	Thermostat wiring	Check G wiring at heat pump. Jumper G and R for fan operation		
	×	X	Fan motor relay	Jumper G and R for fan operation. Check for Line voltage across BR contacts.		
Only Compressor Runs	X	Х	-	Check fan power enable relay operation (if present).		
	Х	Х	Fan motor	Check for line voltage at motor. Check capacitor.		
			The survey of the state of the s	Check thermostat wiring at heat pump. Jumper Y and R for compressor operation		
	×	×	i nermostat wiring	in test mode		
				Set for cooling demand and check 24VAC on RV coil and at CXM/DXM board.		
		X	Reversing valve	If RV is stuck, run high pressure up by reducing water flow and while operating		
				engage and disengage RV coil voltage to push valve.		
Unit Doesn't Operate		Х	Thermostat setup	Check for 'O' RV setup not 'B'.		
in Cooling		Х	Thermostat wiring	Check O wiring at heat pump. Jumper O and R for RV coil 'click'.		
in cooling				Put thermostat in cooling mode. Check 24 VAC on O (check between C and		
		x	Thermostat wiring	O); check for 24 VAC on W (check between W and C). There should be voltage on O, but not on W. If voltage is present on W, thermostat may be bad or wired incorrectly.		

Tranquility® 30 (TT) Series Rev.: October 7, 2016

Performance Troubleshooting

Performance Troubleshooting	Htg	Clg	Possible Cause	Solution
	X	X	Dirty filter	Replace or clean.
				Check for dirty air filter and clean or replace.
	x		Reduced or no air flow in heating	Check fan motor operation and airflow restrictions.
				Too high of external static. Check static vs. blower table.
			Reduced or no air flow in cooling	Check for dirty air filter and clean or replace.
		x		Check fan motor operation and airflow restrictions.
				Too high of external static. Check static vs. blower table.
Insufficient capacity/ Not cooling or heating	x	x	Leaky duct work	Check supply and return air temperatures at the unit and at distant duct registers if significantly different, duct leaks are present.
	X	X	Low refrigerant charge	Check superheat and subcooling per chart.
	X	х	Restricted metering device	Check superheat and subcooling per chart. Replace.
		х	Defective reversing valve	Perform RV touch test.
	X	X	Thermostat improperly located	Check location and for air drafts behind stat.
	X	X	Unit undersized	Recheck loads & sizing. Check sensible clg. load and heat pump capacity.
	Х	х	Scaling in water heat exchanger	Perform scaling check and clean if necessary.
	Х	X	Inlet water too hot or too cold	Check load, loop sizing, loop backfill, ground moisture.
	x		Reduced or no air flow in heating	Check for dirty air filter and clean or replace.
				Check fan motor operation and air flow restrictions.
High Head Pressure				Too high of external static. Check static vs. blower table.
		v	Reduced or no water flow in cooling	Check pump operation or valve operation/setting.
		^		Check water flow. Adjust to proper flow rate.
		х	Inlet water too hot	Check load, loop sizing, loop backfill, ground moisture.
	X		Air temperature out of range in heating	Bring return air temperature within design parameters.
		х	Scaling in water heat exchanger	Perform scaling check and clean if necessary.
	x	x	Unit overcharged	Check superheat and subcooling. Re-weigh in charge.
	X	х	Non-condensables in system	Vacuum system and re-weigh in charge.
	X	X	Restricted metering device.	Check superheat and subcooling per chart. Replace.
Low Suction Pressure	x		Reduced water flow in heating.	Check pump operation or water valve operation/setting.
				Plugged strainer or filter. Clean or replace.
				Check water flow. Adjust to proper flow rate.
	X		Water temperature out of range.	Bring water temperature within design parameters.
				Check for dirty air filter and clean or replace.
		x	Reduced air flow in cooling.	Check fan motor operation and air flow restrictions.
				Too high of external static. Check static vs. blower table.
		X	Air temperature out of range	Too much cold vent air? Bring entering air temperature within design parameters.
	X	X	Insufficient charge	Check for refrigerant leaks.
Low Discharge Air Temperature in Heating	X		Too high of air flow	Check fan motor speed selection and air flow chart.
	X		Poor performance	See 'Insufficient Capacity'
High humidity		X	Too high of air flow	Check fan motor speed selection and airflow chart.
		X	Unit oversized	Recheck loads & sizing. Check sensible clg load and heat pump capacity.

CLIMATEMASTER WATER-SOURCE HEAT PUMPS

Tranquility® 30 (TT) Series Rev.: October 7, 2016

Start-Up Log Sheet

Installer: Complete unit and system checkout and follow unit start-up procedures in the IOM. Use this form to record unit information, temperatures and pressures during start-up. Keep this form for future reference.

Job Name:	Street Address:					
Model Number:	Se	rial Number:				
Unit Location in Building:						
Date:	Sales Order No:					
In order to minimize troublesho the system is put into full opera	poting and costly systemation.	em failures, complete the	e following checks and data en	tries before		
Fan Motor: CFM Settings (E0	CM)					
Temperatures: F or C		Antifreeze	:%			
Pressures: PSIG or kPa		Туре				
	Cooling	Mode	Heating Mode			
Entering Fluid Temperature						
Leaving Fluid Temperature						
Temperature Differential						
Return-Air Temperature	DB	WB		DB		
Supply-Air Temperature	DB	WB		DB		
Temperature Differential						
Water Coil Heat Exchanger (Water Pressure IN)						
Water Coil Heat Exchanger (Water Pressure OUT)						
Pressure Differential						
Water Flow GPM						
Compressor						
Amps						
Volts						
Discharge Line Temperature						
Motor		1				
Amps						
Volts						

Allow unit to run 15 minutes in each mode before taking data.

Note: Never connect refrigerant gauges during startup procedures. Conduct water-side analysis using P/T ports to determine water flow and temperature difference. If water-side analysis shows poor performance, refrigerant troubleshooting may be required. Connect refrigerant gauges as a last resort.

Tranquility® 30 (TT) Series Rev.: October 7, 2016

Functional Troubleshooting



Note: Never connect refrigerant gauges during startup procedures. Conduct water-side analysis using P/T ports to determine water flow and temperature difference. If water-side analysis shows poor performance, refrigerant troubleshooting may be required. Connect refrigerant gauges as a last resort.