## **Manhole Steps**

## **PS1-PF Manhole Step**

Item# - 004-501

Qty - 30 pieces per box, 750 pieces per pallet

Tread Width -10-3/4" (273 mm)

Projection from Wall – 5-3/4" (146 mm)

Leg Center Dimension – 10" (254 mm)

PS1-PF Manhole Steps are designed to be driven into a preformed hole created by a Step Insert, Cam Pin or by Drilling. Minimum Embedment into the concrete is 3".





## **PS1-PF Double Faced Manhole Step**

Item# - 004-501-DF

Qty – 30 pieces per box, 750 pieces per pallet

Tread Width - 10-1/2" (273 mm)

Projection from Wall – 5-3/4" (146 mm)

Leg Center Dimension – 10" (254 mm)

PS1-PF-DF Manhole Steps are designed to be driven into a preformed hole created by a Step Insert, Cam Pin or by Drilling. This step is double sided and cannot be driven in upside down. Minimum embedment into the concrete is 3".

## PS1-DI Manhole Step

Item# - 004-505

Qty - 25 pieces per box, 625 pieces per pallet

Tread Width -10-3/4" (273 mm)

Projection from Wall – 5-3/8" (137 mm)

Leg Center Dimension – 10" (254 mm)

Leg Embedment – 4-3/8" (111 mm)

PS1-DI Manhole Steps are designed to be driven into Green (uncured) concrete. This step is used in Dry Cast Operations. Minimum Embedment into the concrete is 3".

